

GOVERNMENT OF PUDUCHERRY
RAJIV GANDHI GOVERNMENT WOMEN AND CHILDREN HOSPITAL
[O/o. AB-PMJAY and Quality & Safety]
ELLAIPILLAICHAAVADY, PUDUCHERRY – 605 005.

NIQ No.:RGGWCH/AB-PMJAY/ART-Civil Work/2025-26/240 Date: 06-04-2026.

NOTICE INVITING QUOTATIONS FOR PARTITION, REPAIR WORKS AND PAINTING IN NEW ART CLINIC AT 4TH FLOOR

Quotations are invited for Partition, Repair Works and Painting in New ART Clinic at 4th Floor of this Hospital as per annexure.

2. Under the terms and conditions detailed below, quotations may be submitted **on or before 22.04.2026 till 4.00 p.m. by post/in person** furnishing the competitive rates, for the works as per Annexure, in a closed envelope addressed to the "Medical Superintendent, Rajiv Gandhi Government Women and Children Hospital, Ellaipillaichavady, Puducherry – 605 005, and with "**Quotation for Partition, Repair Works & Painting**" marked on it:

- i. **The rates quoted by the contractor shall be for the works as mentioned in the Annexure which includes the materials and other items required for the works.** The rates quoted shall be inclusive of insurance charges, if any. No insurance charges, like transit insurance, etc., will be paid by the purchaser. The contractor shall be solely responsible for the safe delivery of goods in good condition. However, GST may be charged as applicable.
- ii. **The rates once quoted and approved shall be final and valid for one year from the date of finalization of the lowest bidder. No violation will be accepted in this regard.**
- iii. The materials items to be used in the work shall conform to I.S. Standard.
- iv. The works to be carried out shall be strictly in accordance with the specifications mentioned in the work order. Any item, which is not up to the specification or is damaged, will have to be reworked by the contractor at their own cost.
- v. The work shall be commenced immediately after the issue of work order in the place as mentioned in the work order at Rajiv Gandhi Government Women and Children Hospital, Ellaipillaichaavady, Puducherry - 605 005, by the safest mode. **If work is not commenced within two days, the order placed with L1 shall stand cancelled and be placed with L2 without any notice to L1. No further correspondence shall be entertained from L1 and this Hospital will not take any responsibility for any loss.**
- vi. The details of company's account for payment through the Electronic Clearing Service (ECS) and other important nos. under the GST regime and PAN shall be mandatorily mentioned in the quotation.
- vii. The quotations received either by post or in person after the due date and time shall be summarily rejected. The quotations received for part of the work execution will also be summarily be rejected.

3. The Payment through the ECS will be made after the completion of works in good condition and after the receipt of pre-receipted, stamped bill in duplicate.


Medical Superintendent

To

1. For Display in Notice Board.
2. For Hosting in DHFWS / Hospital Website.

ANNEXURE

Name of Work: Assisted Reproductive Technology Clinic at Rajiv Gandhi Government Women & Child Hospital in Puducherry.						
DETAILS FOR ESTIMATE						
Sl.No	Description of items	No	Length	Breath	Depth	Quantity
1	Providing and laying autoclaved aerated concrete blocks masonry					
	Toilet Wall	1 x 1	2.63	0.12	2.20	0.69
	Deduct Door	1 x -2	0.70	0.12	2.10	-0.35
	Duct open	1 x 1	0.90	0.12	2.10	0.23
	Total					0.57 cum
2	Providing and fixing Ist quality ceramic glazed wall tiles					
	Toilet Wall tiles	1 x 1	0.45		1.80	0.81
	Toilet Wall tiles	1 x 1	0.60		1.80	1.08
	Total					1.89 sqm
3	Providing and fixing IS : 12817 marked stainless steel butt hinges					
	Pvc Door	4 x 7				28.00
	Aluminium Door	3 x 10				30.00
	Total					58.00 nos
4	Providing and fixing aluminium sliding door bolts 300 X 16 mm					
	Main Door & Door	1 x 10				10.00
	Total					10.00 nos
5	Providing and fixing aluminium tower bolts - 300 x10 mm					
	Main Door & Door	1 x 4				4.00
	Total					4.00 nos
6	Providing and fixing aluminium tower bolts - 250 x10 mm					
	Door	1 x 4				4.00
	Total					4.00 nos
7	Providing and fixing aluminium tower bolts - 100 x10 mm					
	PVC -Door	1 x 4				4.00
	Pvc Door	2 x 7				14.00
	Aluminium Door	2 x 6				12.00
	Total					30.00 nos
8	Providing and fixing aluminium universal hydraulic door closer					
	Main Door & Door	1 x 4				4.00
	Total					4.00 nos
9	Providing and fixing aluminium handles- 125 mm					
	Pvc Door	1 x 10				10.00
	Total					10.00 nos
10	Providing and fixing aluminium hanging floor door stopper Single					
	Pvc Door	1 x 5				5.00
	Total					5.00 nos
11	Providing and fixing factory made P.V.C. door frame of					
	Room No 562 toilet door frame	1 x 2	4.80			9.60
	Total					9.60 metre

12	Providing and fixing factory made panel PVC door shutter					
	Room No 562 toilet door shutter	1	x	2	0.76	2.02
	Room No 567 toilet door shutter	1	x	1	0.67	1.98
	Room No 566 toilet door shutter	1	x	2	0.77	2.03
	Room No 561 toilet door shutter	1	x	2	0.77	1.18
	Total					9.35 sqm

13	Providing and fixing factory made UPVC white colour sliding window					
	Entrance Window	1	x	1	1.80	1.60
	Nursing station Window	1	x	2	1.80	1.60
	Room 571	1	x	1	1.40	1.60
	Room 570	1	x	1	1.65	1.60
	Room 567	1	x	1	1.80	1.40
	Room 566	1	x	2	1.80	1.60
	Room 562	1	x	2	1.20	1.40
	Room 561	1	x	1	1.80	1.60
	Total					28.04 sqm

14	Providing and fixing stainless steel (grade 304) railing made hollow tubes					
	Entrance door Screen rod 25mm dia	1	x	1	2.10	0.485 kg/m
	Varandha window Screen rod 25mm	1	x	1	2.00	0.485 kg/m
	Nursing Room Screen rod 25mm	1	x	2	2.00	0.485 kg/m
	R-571 Screen rod 25mm	1	x	1	1.13	0.485 kg/m
	R-571 Screen rod 25mm	1	x	1	2.97	0.485 kg/m
	R-570 Screen rod 25mm	1	x	1	1.60	0.485 kg/m
	R-570 Screen rod 25mm	1	x	1	2.63	0.485 kg/m
	R-567 Screen rod 25mm	1	x	1	2.00	0.485 kg/m
	R-566 Screen rod 25mm	1	x	2	2.00	0.485 kg/m
	R-561 Screen rod 25mm	1	x	1	5.80	0.485 kg/m
	R-561 Screen rod 25mm	1	x	1	3.00	0.485 kg/m
	R-561 Screen rod 25mm V	1	x	2	0.90	0.485 kg/m
	R-561 Screen rod 25mm	1	x	2	1.40	0.485 kg/m
	R-561 Screen rod 25mm	1	x	1	2.00	0.485 kg/m
	R-562 Screen rod 25mm	1	x	2	2.00	0.485 kg/m
	R-563 Screen rod 25mm	1	x	2	2.00	0.485 kg/m
	R-564 Screen rod 25mm	1	x	2	1.50	0.485 kg/m
	R-565 Screen rod 25mm	1	x	1	2.00	0.485 kg/m
	Total					24.67 kg

15	Providing and fixing fly proof wire gauze Windows, clerestory					
	Window Special ward	3	x	3	0.50	1.45
	Ventilator	1	x	5	0.90	0.50
	Total					8.78 sqm

16	Providing and fixing glass panes with putty - 5mm thick glass panes					
	Entrance Window	1	x	3	0.49	1.40
	Nursing station Window	2	x	3	0.50	1.40
	Room 571	1	x	2	0.45	1.42
	Room 570	1	x	3	0.45	1.40
	Room 567	1	x	3	0.50	1.23
	Room 566	2	x	3	0.52	1.23
	Room 562	2	x	2	0.51	1.25

	Room 561	1	x	3	0.50		1.45	2.18
	Emergency Exit	1	x	1	0.85		0.69	0.59
	Emergency Exit	1	x	1	0.85		0.30	0.26
	Counter	1	x	1	0.45		0.30	0.14
	Corridor door	3	x	2	1.08		0.41	2.66
	Total							23.50 sqm
17	Providing and fixing unplasticised - PVC pipe clips of -75mm							
	PVC -Door	1	x	8				8.00
	Total							8.00 nos
18	12 mm cement plaster of mix 1:5 (1 cement : 5 fine aggregate)							
	Toilet floor tiles	1	x	1	1.37		1.30	1.78
	Toilet Wall	1	x	1	2.63		2.20	5.79
	Deduct Door	1	x	-2	0.70		2.10	-2.94
	Add Door jams	1	x	2	4.90		0.12	1.18
	Duct open	1	x	1	0.90		2.10	1.89
	Total							7.70 sqm
19	Providing and fixing 1st quality ceramic glazed floor tiles							
	Toilet floor tiles	1	x	1	1.37	1.30		1.78
	Total							1.78 sqm
20	Finishing with deluxe multi surface paint system for interiors							
	Qty as per code 14.46							1005.00
	Total							1005.00 sqm
21	Painting with synthetic enamel paint of shade - Two or more coats on new work							
	Entrance Window grill	1	x	1	1.80	1.00	1.60	2.88
	Nursing station Window grill	1	x	2	1.80	1.00	1.60	5.76
	Room 571 Window grill	1	x	1	1.40	1.00	1.60	2.24
	Room 570 Window grill	1	x	1	1.65	1.00	1.60	2.64
	Room 567 Window grill	1	x	1	1.80	1.00	1.40	2.52
	Room 566 Window grill	1	x	2	1.80	1.00	1.60	5.76
	Room 565 Window grill	1	x	1	1.80	1.00	1.60	2.88
	Room 565 Window grill Arch	1	x	1	1.00	1.00	0.50	0.50
	Room 564 Window grill	1	x	1	1.20	1.00	1.40	1.68
	Room 563 Window grill	1	x	1	1.20	1.00	1.40	1.68
	Room 562 Window grill	1	x	2	1.20	1.00	1.40	3.36
	Room 561 Window grill	1	x	1	1.80	1.00	1.60	2.88
	Room 561 Window grill	1	x	1	1.00	1.00	0.22	0.22
	Total							35.00 sqm
22	Providing and applying white cement based putty of average 1mm tk							
	Qty as per code 14.46							1005.00
	Total							1005.00 sqm

23	Polishing on wood work with ready made wax polish of - Old work							
	Door	1	x	7	1.20	2.40	2.07	41.73
	Door ventilator	1	x	7	1.20	1.00	0.30	2.52
	Door	1	x	4	1.00	2.40	2.07	19.87
	Door ventilator	1	x	4	1.00	1.00	0.30	1.20
	Door 566	1	x	2	0.90	1.00	2.10	3.78
	Door 565	1	x	2	0.90	1.00	2.10	3.78
	Door 561	1	x	2	0.90	1.00	2.10	3.78
	Total							76.66 sqm
24	Removing dry or oil bound distemper, water proofing cement paint							
	Entrance	1	x	1	3.90	0.30		1.17
	Entrance	1	x	1	1.60		2.55	4.08
	Entrance Varandha	1	x	1	3.95		0.88	3.48
	Deduct Window (-)	1	x	-1	1.80		0.57	-1.03
	Entrance Varandha N&S	1	x	2	5.75		0.88	10.12
	Deduct Door (-)	1	x	-1	2.08		0.58	-1.21
	Add Jams	1	x	1	3.24	0.14		0.45
	East wall	1	x	1	3.95		0.88	3.48
	Beam both side	1	x	2	2.54		0.27	1.37
	Deduct Open (-)	1	x	-1	2.54		0.60	-1.52
	Nursing Station N&S	1	x	2	5.95		0.80	9.52
	Deduct Window (-)	1	x	-1	1.80		0.55	-0.99
	Deduct Box (-)	1	x	-1	0.60		0.40	-0.24
	Deduct Box (-)	1	x	-1	0.65		0.22	-0.14
	Wall East	1	x	1	3.15		0.83	2.61
	Add Jams Opening	1	x	2	0.55		0.30	0.33
	Add Beam	1	x	1	3.15		0.57	1.80
	Varandha South	1	x	1	2.35		0.83	1.95
	Deduct Window (-)	1	x	-1	1.80		0.59	-1.06
	Add Jams	1	x	1	6.80		0.30	2.04
	Varandha	1	x	1	2.30		0.25	0.58
	Varandha	1	x	2	9.05		0.25	4.53
	Room-571 Ceiling	1	x	1	6.03	2.93		17.67
	Wall N&S	1	x	2	6.03		1.54	18.57
	Wall East & West	1	x	2	2.93		1.54	9.02
	Deduct Window (-)	1	x	-1	1.14		0.57	-0.65
	Add Jams Window	1	x	1	5.48		0.14	0.77
	Deduct Door (-)	1	x	-1	1.00		0.55	-0.55
	Add Jams Door	1	x	1	5.80		0.14	0.81
	Add Jams Column	1	x	2	0.56		1.55	1.74
	Add Jams Column	1	x	2	0.46		1.55	1.43
	Room-570 Ceiling	1	x	1	2.63	5.80		15.25
	Wall N&S	1	x	2	5.80		1.54	17.86
	Wall East & West	1	x	2	2.63		1.54	8.10
	Deduct Window (-)	1	x	-1	1.61		0.45	-0.72
	Add Jams Window	1	x	1	6.42		0.14	0.90
	Deduct Door (-)	1	x	-1	1.00		0.55	-0.55
	Add Jams Door	1	x	1	5.80		0.14	0.81
	Room-569 Ceiling	1	x	1	2.21	5.80		12.82
	Wall N&S	1	x	2	5.80		1.54	17.86

Wall East & West	1	x	2	2.63		1.54	8.10
Deduct Door (-)	1	x	-1	0.90		0.55	-0.50
Add Jams Door	1	x	1	5.70		0.14	0.80
Room-568 Ceiling	1	x	1	2.92	6.00		17.52
Wall N&S	1	x	2	6.00		1.55	18.60
Wall East & West	1	x	2	2.92		1.55	9.05
Deduct (-)	1	x	-1	2.45		0.58	-1.42
Add Jams Door	1	x	1	6.06		0.14	0.85
Room-567 Ceiling	1	x	1	4.55	5.85		26.62
Wall N&S	1	x	2	5.85		1.55	18.14
Wall East & West	1	x	2	4.55		1.55	14.11
Cross Wall	1	x	2	1.60		1.55	4.96
Cross Wall	1	x	2	2.55		1.55	7.91
Deduct Window (-)	1	x	-1	1.80		0.30	-0.54
Deduct Window Arch (-)	1	x	-1	1.10		0.50	-0.55
Room-566 Ceiling	1	x	1	5.80	6.28		36.42
Beam both side	1	x	2	5.80		0.45	5.22
Wall	1	x	2	5.80		1.55	17.98
Wall	1	x	2	6.28		1.55	19.47
Deduct Window (-)	1	x	-1	1.80		0.30	-0.54
Deduct Window Arch (-)	1	x	-1	1.10		0.50	-0.55
Deduct Open (-)	1	x	-1	1.41		0.55	-0.78
Toilet ceiling	1	x	1	3.54	1.55		5.49
Toilet Wall	1	x	2	3.54		1.55	10.97
Toilet Wall	1	x	1	1.41		1.55	2.19
Toilet Wall	1	x	1	1.41		1.00	1.41
Deduct Door (-)	1	x	-1	1.10		0.56	-0.62
Add Door Jams	1	x	1	5.90		0.14	0.83
Toilet ceiling	1	x	1	4.00	3.30		13.20
Wall	1	x	2	4.00		1.55	12.40
Wall	1	x	2	3.30		1.55	10.23
Duct Side	1	x	2	0.73		1.55	2.26
Deduct Window (-)	1	x	-1	1.80		0.30	-0.54
Deduct Window Arch (-)	1	x	-1	1.10		0.50	-0.55
Deduct Door (-)	1	x	-1	1.10		0.55	-0.61
Add Door Jams	1	x	1	5.90		0.14	0.83
Add Window Jams	1	x	1	6.80		0.14	0.95
Emergency Exit Ceiling	1	x	1	6.16		1.00	6.16
Emergency Exit Wall	1	x	2	6.16		0.96	11.83
Room-565 ceiling	1	x	1	5.60	5.85		32.76
Wall	1	x	2	5.60		1.55	17.36
Wall	1	x	2	5.85		1.55	18.14
Deduct Window (-)	1	x	-1	1.80		0.30	-0.54
Deduct Window Arch (-)	1	x	-1	1.10		0.50	-0.55
Deduct Door (-)	1	x	-1	1.20		0.55	-0.66
Deduct Open (-)	1	x	-1	1.20		0.55	-0.66
Add Door Jams	1	x	1	5.90		0.14	0.83
Add Window Jams	1	x	1	6.80		0.14	0.95
Add Open Jams	1	x	1	6.80		0.14	0.95
Toilet ceiling	1	x	1	3.27	5.90		19.29
Wall	1	x	2	3.27		1.55	10.14
Wall	1	x	2	5.90		1.55	18.29

Deduct Window (-)	1	x	-1	1.80		0.50	-0.90
Deduct Door (-)	1	x	-1	1.20		0.50	-0.60
Room-564 ceiling	1	x	1	4.13	5.85		24.16
Wall	1	x	2	4.13		1.55	12.80
Wall	1	x	2	5.85		1.55	18.14
Deduct Window (-)	1	x	-1	1.20		0.50	-0.60
Deduct Door (-)	1	x	-1	1.20		0.50	-0.60
Add Door Jams	1	x	1	6.00		0.14	0.84
Add Window Jams	1	x	1	5.60		0.14	0.78
Add Toilet wall	1	x	2	1.60		1.55	4.96
Add Toilet wall	1	x	2	2.60		1.55	8.06
Deduct toilet	1	x	-1	0.90		0.30	-0.27
Deduct toilet Ventilator	1	x	-1	0.90		0.45	-0.41
Room-563 ceiling	1	x	1	6.10	5.80		35.38
Wall	1	x	2	6.10		1.55	18.91
Wall	1	x	2	5.80		1.55	17.98
Deduct Window (-)	1	x	-1	1.20		0.40	-0.48
Deduct Door (-)	1	x	-1	1.20		0.57	-0.68
Deduct Door toilet (-)	1	x	-1	1.00		0.57	-0.57
Add Door Jams	1	x	1	6.00		0.14	0.84
Add Window Jams	1	x	1	5.60		0.14	0.78
Add Beam	1	x	2	5.80		0.50	5.80
Toilet ceiling	1	x	1	2.75	5.85		16.09
Add Toilet wall	1	x	2	2.75		1.55	8.53
Add Toilet wall	1	x	2	5.85		1.55	18.14
Deduct toilet	1	x	-2	0.90		0.30	-0.54
Room-562 ceiling	1	x	1	6.75	5.82		39.29
Wall	1	x	2	6.75		1.55	20.93
Wall	1	x	2	5.82		1.55	18.04
Add duct Wall	1	x	2	0.75		1.55	2.33
Deduct Window (-)	1	x	-2	1.20		0.55	-1.32
Deduct Door (-)	1	x	-1	1.20		0.50	-0.60
Deduct Door toilet (-)	1	x	-1	1.00		0.50	-0.50
Add Door Jams	1	x	1	6.00		0.14	0.84
Add Window Jams	1	x	1	5.60		0.14	0.78
Add Beam	1	x	2	5.80		0.50	5.80
Toilet ceiling	1	x	1	2.82	5.84		16.47
Add Toilet wall	1	x	2	2.82		1.55	8.74
Add Toilet wall	1	x	2	5.84		1.55	18.10
Deduct Ventilator toilet	1	x	-1	0.90		0.45	-0.41
Add Toilet wall	1	x	4	1.60		0.23	1.47
Add Toilet wall	1	x	2	0.55		0.23	0.25
Add Toilet wall	1	x	4	0.38		0.23	0.35
Add Toilet wall top	1	x	4	2.53		0.23	2.33
Room-561 ceiling	1	x	1	6.80	5.80		39.44
Wall	1	x	2	6.80		1.55	21.08
Wall	1	x	2	5.80		1.55	17.98
Add Column	1	x	2	0.60		1.55	1.86
Deduct Window (-)	1	x	-2	1.80		0.55	-1.98
Deduct Door (-)	1	x	-1	1.20		0.50	-0.60
Deduct Door toilet (-)	1	x	-1	1.00		0.50	-0.50
Add Door Jams	1	x	1	6.00		0.14	0.84

	Add Window Jams	1	x	1	5.60		0.14	0.78
	Add Beam	1	x	2	5.80		0.50	5.80
	Toilet ceiling	1	x	1	2.75	5.80		15.95
	Add Toilet wall	1	x	2	2.75		1.55	8.53
	Add Toilet wall	1	x	2	5.80		1.55	17.98
	Deduct Ventilator toilet	1	x	-1	0.90		0.45	-0.41
	Add Toilet wall	1	x	4	1.65		0.23	1.52
	Add Toilet wall	1	x	3	0.38		0.23	0.26
	Add Toilet wall top	1	x	1	2.53		0.23	0.58
	Add wall	1	x	1	1.00		0.40	0.40
	Total							<u>1005.00</u> sqm
25	Demolishing brick work manually / by mechanical means including							
	Toilet cross wall	1	x	1	2.63	0.15	2.20	0.87
	Duct wall	1	x	1	0.90	0.15	2.20	0.30
	Total							<u>1.17</u> cum
26	Dismantling steel work in built up sections in angles, tees, flats							
	Entrance Window grill	1	x	1	1.80	35.00	1.60	100.80
	Nursing station Window grill	1	x	2	1.80	35.00	1.60	201.60
	Room 571 Window grill	1	x	1	1.40	35.00	1.60	78.40
	Room 570 Window grill	1	x	1	1.65	35.00	1.60	92.40
	Room 567 Window grill	1	x	1	1.80	35.00	1.40	88.20
	Room 566 Window grill	1	x	2	1.80	35.00	1.60	201.60
	Room 565 Window grill	1	x	1	1.80	35.00	1.60	100.80
	Room 565 Window grill Arch	1	x	1	1.00	35.00	0.50	17.50
	Room 564 Window grill	1	x	1	1.20	35.00	1.40	58.80
	Room 563 Window grill	1	x	1	1.20	35.00	1.40	58.80
	Room 562 Window grill	1	x	2	1.20	35.00	1.40	117.60
	Room 561 Window grill	1	x	1	1.80	35.00	1.60	100.80
	Room 561 Window grill	1	x	1	1.00	35.00	0.22	7.70
	Total							<u>1225.00</u> kg
27	Dismantling tile work in floors and roof of tiles 10mm to 25mm							
	Toilet Wall tiles	1	x	1	0.45		1.80	0.81
	Toilet Wall tiles	1	x	1	0.60		1.80	1.08
	Toilet floor tiles	1	x	1	1.37	1.30		1.78
	Total							<u>3.67</u> sqm
28	Providing and fixing ASTM pipes including all ASTM plain & brass threaded fittings this included jointing of pipes & fittings with one step ASTM solvent cement , trenching refilling & testing of joints complete (External work) - 25 mm nominal outer dia pipes							
	Wash basin line	1	x	1	18.00			18.00
	Total							<u>18.00</u> metre
29	Providing and fixing aluminium work for fixed portion							
	100x50x2mm Room 571 V	1	x	2	1.49	1.62	k/m	4.83
	100x50x2mm Room 571 H	1	x	3	1.30	1.62	k/m	6.32
	100x50x2mm Room 568 V	1	x	2	1.13	1.62	k/m	3.66
	100x50x2mm Room 568 H	1	x	3	1.46	1.62	k/m	7.10

100x50x2mm Room 567 V	1	x	6	2.15	1.62	k/m	20.90
100x50x2mm Room 567 Top	1	x	1	3.32	1.62	k/m	5.38
100x50x2mm Room 567 B&M	1	x	2	2.21	1.62	k/m	7.16
100x50x2mm Room 567 TM&B	1	x	3	1.17	1.62	k/m	5.69
100x50x2mm Room 567 Door-V	1	x	2	2.17	1.62	k/m	7.03
100x50x2mm Room 567 Door-H	1	x	3	1.02	1.62	k/m	4.96
100x50x2mm Corridor Fixed-V	3	x	2	2.60	1.62	k/m	25.27
100x50x2mm Corridor Fixed-H	3	x	2	2.27	1.62	k/m	22.06
100x50x2mm Corridor Fixed-V	3	x	1	0.57	1.62	k/m	2.77
100x50x2mm Corridor Fixed-V	3	x	1	0.57	1.62	k/m	2.77
100x50x2mm Corridor Door-H	3	x	6	1.01	1.62	k/m	29.45
100x50x2mm Corridor Door-V	3	x	4	2.08	1.62	k/m	40.44
100x50x2mm Room 566 -H-bottom	1	x	1	6.26	1.62	k/m	10.14
100x50x2mm Room 566 -H	1	x	3	2.54	1.62	k/m	12.34
100x50x2mm Room 566 -H	1	x	3	1.63	1.62	k/m	7.92
100x50x2mm Room 566 -V	1	x	7	2.14	1.62	k/m	24.27
100x50x2mm Room 566 -Door-V	2	x	2	2.10	1.62	k/m	13.61
100x50x2mm Room 566 -Door-H	2	x	2	1.07	1.62	k/m	6.93
100x50x2mm Room 566 -Door-H	2	x	1	1.07	1.62	k/m	3.47
100x50x2mm Room 566 -Door-H	2	x	1	2.15	1.62	k/m	6.97
100x50x2mm Room 566 Partion-H	1	x	3	4.05	1.62	k/m	19.68
100x50x2mm Room 566 Partion-H	1	x	5	2.10	1.62	k/m	17.01
100x50x2mm Emergency -H	1	x	2	0.96	1.62	k/m	3.11
100x50x2mm Emergency -V	1	x	2	2.33	1.62	k/m	7.55
100x50x2mm Emergency -H	1	x	3	0.89	1.62	k/m	4.33
100x50x2mm Emergency -V	1	x	2	1.96	1.62	k/m	6.35

339.47 kg

90x45x1.6mm Window-H	3	x	3	1.80	1.45	kg/m	23.49
90x45x1.6mm Window-V	3	x	4	1.60	1.45	kg/m	27.84
90x45x1.6mm Window-V	3	x	4	0.50	1.45	kg/m	8.70

60.03 kg

Clips V	1	x	4	0.44	0.027	kg/m	0.05
Clips H	8	x	4	1.21	0.027	kg/m	1.05
Clips V	1	x	4	0.91	0.027	kg/m	0.10
Clips V	1	x	4	1.37	0.027	kg/m	0.15
Clips V	1	x	4	1.67	0.027	kg/m	0.18
Clips H	1	x	4	1.05	0.027	kg/m	0.11
Clips V	1	x	4	0.92	0.027	kg/m	0.10
Clips H	1	x	4	0.92	0.027	kg/m	0.10
Clips V	1	x	4	0.98	0.027	kg/m	0.11
Clips V	3	x	4	1.05	0.027	kg/m	0.34
Clips V	3	x	4	1.08	0.027	kg/m	0.35
Clips H	3	x	4	1.05	0.027	kg/m	0.34
Clips H	3	x	4	0.90	0.027	kg/m	0.29
Clips V	3	x	8	0.41	0.027	kg/m	0.27
Clips H	3	x	8	1.08	0.027	kg/m	0.70
Clips V	3	x	8	0.92	0.027	kg/m	0.60
Clips V	3	x	8	0.99	0.027	kg/m	0.64
Clips H	3	x	8	0.80	0.027	kg/m	0.52
Clips H	3	x	8	0.92	0.027	kg/m	0.60
Clips H	2	x	8	0.96	0.027	kg/m	0.41
Clips V	2	x	4	1.05	0.027	kg/m	0.23

Clips V	2	x	4	0.80	0.027	kg/m	0.17
Clips V	1	x	16	1.20	0.027	kg/m	0.52
Clips H	1	x	8	1.09	0.027	kg/m	0.24
Clips H	1	x	8	0.91	0.027	kg/m	0.20
Clips V	1	x	16	0.74	0.027	kg/m	0.32
Clips H	1	x	8	1.09	0.027	kg/m	0.24
Clips H	1	x	8	0.91	0.027	kg/m	0.20
Clips H	1	x	24	0.91	0.027	kg/m	0.59
Clips V	1	x	16	1.09	0.027	kg/m	0.47
Clips V	1	x	16	0.91	0.027	kg/m	0.39
Clips H	1	x	4	0.87	0.027	kg/m	0.09
Clips V	1	x	4	0.28	0.027	kg/m	0.03
Clips H	1	x	8	0.69	0.027	kg/m	0.15
Clips V	1	x	4	0.85	0.027	kg/m	0.09
Clips V	1	x	4	0.79	0.027	kg/m	0.09
							11.03 kg
L -Clamp	1	x	250	0.15	kg/no		37.50 kg
Channel 50x50x2mm	1	x	2	0.96	1.40	kg/m	2.69
Channel	1	x	2	0.31	1.40	kg/m	0.87
Channel	1	x	2	0.43	1.40	kg/m	1.20
							4.76 kg
Total							<u>452.79 kg</u>
30	Providing and fixing 12 mm thick prelaminate particle board						
Entrance door	1	x	2	0.80		0.70	1.12
Room No 571 Partion	1	x	1	1.21		0.44	0.53
Room No 571 Partion	1	x	1	1.21		0.91	1.10
Room No 568 partion	1	x	1	1.37		0.67	0.92
Room No 568 partion	1	x	1	0.95		0.29	0.28
Room No 567 Door	1	x	1	0.90		1.04	0.94
Room No 567 Door	1	x	1	0.90		0.80	0.72
Room No 567 Partion	1	x	1	1.05		1.10	1.16
Room No 567 Partion	1	x	1	1.05		0.90	0.95
Room No 567 Partion	1	x	1	1.05		1.10	1.16
Room No 567 Partion	1	x	1	1.05		0.90	0.95
Room No 567 Partion	1	x	1	1.04		1.10	1.14
Room No 567 Partion	1	x	1	0.94		0.90	0.85
Corridor door	3	x	2	0.92		0.99	5.46
Corridor door	3	x	2	0.92		0.80	4.42
Room No 566 Door	1	x	2	0.96		1.04	2.00
Room No 566 Door	1	x	2	0.96		0.78	1.50
Room No 566 Partion	1	x	2	1.20		1.09	2.62
Room No 566 Partion	1	x	2	1.20		0.91	2.18
Room No 566 Partion	1	x	2	1.09		0.74	1.61
Room No 566 Partion	1	x	2	0.91		0.74	1.35
Room No 566 Partion	1	x	3	0.91		1.09	2.98
Room No 566 Partion	1	x	1	1.09		1.09	1.19
Room No 566 Partion	1	x	1	1.09		0.91	0.99
Room No 566 Partion	1	x	1	0.91		0.91	0.83
Emergency Exit door	1	x	1	0.69		0.79	0.55
Total							<u>39.50 sqm</u>

31	Providing, laying and jointing UPVC pipes - 75mm dia.					
	Wash basin line	1	x	1	18.00	18.00
	Total					18.00 metre
32	Providing and fixing in position UPVC equal Tee -75mm dia					
	PVC -Door	1	x	1		1.00
	Total					1.00 nos
33	Providing and fixing in position UPVC plain coupler- 75mm dia					
	PVC -Door	1	x	1		1.00
	Total					1.00 nos
34	Providing and fixing in position UPVC elbow- 75mm dia					
	PVC -Door	1	x	10		10.00
	Total					10.00 nos
35	Providing and fixing expanded polystyrene (50 mm thick)					
	False ceiling	1	x	40	0.60	0.60
	Total					14.40 sqm
36	PVC switch lock of 100mm length					
	PVC -Door	1	x	25		25.00
	Total					25.00 nos


MEDICAL SUPERINTENDENT
 Rajiv Gandhi Govt. Women & Children Hospital
 Puducherry.