

GOVERNMENT OF PUDUCHERRY
RAJIV GANDHI GOVERNMENT WOMEN AND CHILDREN HOSPITAL
(AB-PMJAY – Quality & Safety Office)
ELLAIPILLAICHAADVY, PUDUCHERRY – 605 005.

NIQ No.: RGGWCH/AB-PMJAY/BMWSA Repair/2024-25/¹⁴⁵ Date: 31-01-2025.

**NOTICE INVITING QUOTATIONS FOR REPAIRING WORKS IN BIO-MEDICAL
WASTE STORAGE AREA OF THIS HOSPITAL**

Quotations are invited for Repairing Works in Bio-Medical Waste Storage Area of this Hospital as per annexure.

2. Under the terms and conditions detailed below, quotations may be submitted on or before 10.02.2025 till 4.00 p.m. by post/in person furnishing the competitive rates, for the works as per Annexure, in a closed envelope addressed to the "Medical Superintendent, Rajiv Gandhi Government Women and Children Hospital, Ellaipillaichavady, Puducherry – 605 005, and with "Quotation for Bio Medical Waste Storage Area Repairs" marked on it:

- i. The rates quoted by the firm/contractor shall be for the works as mentioned in the Annexure which includes the materials and other items required for the works. The rates quoted shall be inclusive of insurance charges, if any. No insurance charges, like transit insurance, etc., will be paid by the purchaser. The firm/contractor shall be solely responsible for the safe delivery of goods in good condition. However, GST may be charged as applicable.
- ii. The rates once quoted and approved shall be final and valid for one year from the date of finalization of the lowest bidder. No violation will be accepted in this regard.
- iii. The materials/items to be used in the work shall conform to I.S. standard.
- iv. The works to be carried out shall be strictly in accordance with the specifications mentioned in the work order. Any item, which is not up to the specification or is damaged, will have to be reworked by the firm/contractor at their own cost.
- v. The work shall be commenced immediately after the issue of work order in the place, as mentioned in the work order, at Rajiv Gandhi Government Women and Children Hospital, Ellaipillaichavady, Puducherry – 605 005, by the safest mode. If work is not commenced within two days, the order placed with L1 shall stand cancelled and be placed with L2 without any notice to L1. No further correspondence shall be entertained from L1 and this Hospital will not take any responsibility for any loss.
- vi. The details of company's account for payment through the Electronic Clearing Service (ECS) and other important nos. under the GST regime and PAN shall be mandatorily mentioned in the quotation.
- vii. The firm can, if wishes to, inspect the site on any working day on prior intimation and with prior permission before submission of quotation.
- viii. The prices offered in the quotation should include all the charges and not separate charges except GST will be paid by this Hospital.
- ix. The quotations received either by post or in person after the due date and time shall be summarily rejected.

3. The Payment through the ECS will be made after the completion of works in good condition and after the receipt of pre-receipted, stamped bill in duplicate.


MEDICAL SUPERINTENDENT

To

1. For Display in Notice Board.
2. For Hosting in Directorate / Hospital Website.

ANNEXURE

SPECIFICATION FOR REPAIRING WORKS IN BIO MEDICAL WASTE STORAGE

AREA (02 Rooms)

1	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to ISS :4454 - part 1 and M.S. top cover of required thickness for rolling shutters - 80 x 0.90 mm M.S. laths with 0.90 mm thick top cover — 16.70 sqm.
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead - for thickness of tiles 10mm to 25mm — 38 sqm
3	Providing and laying vitrified floor tiles of size 600 x600 mm (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622 of approved make , in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement : 4 fine aggregate) ,jointing with grey cement slurry @3.3 kg per sqm including grouting the joints with white cement and matching pigments etc., complete - size of tile 600x600mm — 38 sqm.
4	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade - Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture — 40 sqm.
5	Dismantling doors, Rolling shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead - of area beyond 3 sq.metres — 2 Nos.
6	Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 sq.metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumping ground as per direction of Engineer-in-charge - with cement mortar 1:4 (1 cement : 4fine aggregate) — 2 sqm.
7	Finishing walls with acrylic smooth exterior paint of required shade - New work (two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre / 10 sqm with scrapping the surface — 50 sqm.
8	Disposal of dismantled Floor tiles at Bio medical wastage room and un-serviceable dismantled material around the up to 8km radius. The rate includes charges transportation by manual / means loading and unloading etc, complete as directed by the Engineer in-charge — 3 Cum.

MEDICAL SUPERINTENDENT